



PhilGEPS

Philippine Government Electronic Procurement System

Central Portal for
Philippine Government
Procurement Opportunities

[Help](#)

Bid Notice Abstract

Request for Quotation (RFQ)

Reference Number 13151857
Procuring Entity EASTERN VISAYAS STATE UNIVERSITY-TANAUAN CAMPUS
Title Purchase of Construction Supplies and Materials
Area of Delivery Leyte

Solicitation Number:	PR2026-07-22-060	Status	Closed
Trade Agreement:	Implementing Rules and Regulations		
Procurement Mode:	Negotiated Procurement - Small Value Procurement (Sec. 34)	Associated Components	1
Classification:	Civil Works	Bid Supplements	0
Category:	Construction Materials and Supplies		
Approved Budget for the Contract:	PHP 431,500.00	Document Request List	1
Delivery Period:	7 Day/s		
Client Agency:		Date Published	24/07/2026
Contact Person:	DANIEL G. AMIDA JR. BAC Chairman Havana St., Brgy. San Miguel Pobl. Tanauan Leyte Philippines 6502 63-950-6801496 bac.tanauan@evsu.edu.ph	Last Updated / Time	24/07/2026 00:00 AM
		Closing Date / Time	27/07/2026 01:00 AM

Description

SUPPLY AND DELIVERY OF CONSTRUCTION OF BUSINESS INCUBATION CENTER

ITEM I - PLAIN AND REINFORCED CONCRETE

Estimated Quantity :

A. Materials (Delivered to Jobsite)

150 bags Portland Cement

10 cu.m. Washed Sand

19 cu.m. Washed Gravel

ITEM II - MASONRY WORKS

Estimated Quantity =

Total Estimated Quantity =

A. Materials (Delivered to Jobsite)

1350 pcs. 4" Concrete Hollow Blocks

122 bags Portland Cement

10 cu.m Washed Sand

ITEM III - REINFORCING STEEL

Estimated Quantity = 1 lot

A. Materials (Delivered to Jobsite)

24 pcs. 16mm dia. RSB

ITEM V - ROOFING WORKS

Estimated Quantity:

Total Estimated Area =

A. Materials (Delivered to Jobsite)

40 pcs. Angle Bar 2"x2"

10 pcs. Angle Bar 1/4"x1/2"

26 pcs. G.a 26 Pre-painted Corrugated G.I Sheets 12' .4mm

30 pcs. 1/4" Gusset Plate 6"x 6"

25 pcs. C-Purlins 2"x3"

6 pcs. Ridge Roll

10 kgs. Welding Rod E6013

2 boxes Roof screw 2 1/2"

ITEM VI - Dry Wall Partition

Estimated Quantity:

Total Estimated Area =

A. Materials (Delivered to Jobsite)

32 pcs. Hardiflex (4.5mm)

32 pcs. 19mm x 50mm x 5mm Metal Furring

32 pcs. 25mm x 25mm, 0.4mm thickness Wall angle

2 kgs. 2" Concrete Nails

3 boxes Blind Rivets

ITEM VII- HARDWARE

Estimated Quantity = 1 lot

A Materials (Delivered to Jobsite)

5 kgs. 3" cwn nails

5 kgs. 2" cwn nails

3 kgs. 1" cwn nails

3 kgs. 1" finishing nails

ITEM VIII - CONDUITS,BOXES AND FITTINGS

Estimated Quantity = 1 lot

A Materials (Delivered to Jobsite)

13 pcs. Junction Box 4" x 4" w/ Screw

10 pcs. Utility Box 2" x 4"

10 pcs. PVC ELECT PIPE 3/4

40 pcs. 3/4" dia. PVC Clip

ITEM IX - WIRES AND WIRING DEVICES

Estimated Quantity = 1 lot

A Materials (Delivered to Jobsite)

2 boxes 3.5mm THHN WIRE

1 box 5.5 mm THHN WIRE

13 pcs. Philips 7W (Led Bulb Daylight White)

14 rolls Electrical Tape

13 pcs. Lamp Holder

ITEM X - POWER LOAD CENTER, SWITCHGEAR AND PANEL BOARDS

Estimated Quantity = 1 lot

A Materials (Delivered to Jobsite)

1 pc. 30A,2 poles Circuit Breaker

2 pcs. 20A,2 poles Circuit Breaker

1 pc. 15A,2 poles Circuit Breaker

6 sets One-Gang Switch w/ Plate

1 set Three-Gang Switch w/ Plate

10 sets Two Gang Convenience Outlet

Created by DANIEL G. AMIDA JR.**Date Created** 23/07/2026

The PhilGEPS team is not responsible for any typographical errors or misinformation presented in the system. PhilGEPS only displays information provided for by its clients, and any queries regarding the postings should be directed to the contact person/s of the concerned party.